## Detailed Technical Specifications Sr. No.

08.

Spares

| Sr. No  | Descrip   | tion   | Qty.                       |
|---|---|--|----------------------------|
| 01.   | Main Circulation Pump for TMO test loop   |  | 02                         |
|   | Туре  | Canned Motor Pump  |                            |
|   | Location  | Indoor   |                            |
|   | Working Fluid   | R-134a   |                            |
|   | Flow Rate   | 0 - 1 m <sup>3</sup> /hr. ( (! - 0.3 kg/s)               |                            |
|   | Design Pressure   | 5 MPa (50 bar)   |                            |
|   | Design Temperature  | 150 °C   |                            |
|   | NPSH <sub>6</sub>   | 3 m  |                            |
|   | Suction & Discharge Port Diameters  | ~ DN 15 mm   |                            |
|   | Operating Temperature Range   | 10 - 100 °C  |                            |
|   | Differential Head   | 30 m   |                            |
|   | Motor I   |  |                            |
|   | Motor Type:   | VFD Controlled (Compatible with Pump Model)              |                            |
|   | Phase / Voltage / Frequency   | 3 Ph / 400V / 50 Hz                                      | ]                          |
|   | Orientation   | Horizontal   |                            |
|   | Motor type/Connection   | 3 phase/DOL  | _                          |
|   | Type of Starting  Permissible Phase Unbalance in Supply   | Direct Online  | -                          |
|   | Voltage   | < 5%   | 1                          |
|   | Enclosure and Degree of Protection  | IP-65  | -                          |
|   | Material of Co  |  | 1                          |
|   | body and all wetted parts   | 33-3 to C or righter grades                              |                            |
| 02.   | VFD Controller  |  | 02                         |
| 03.   | Counter flanges   |  | For 02<br>Pumps            |
| 04.   | Base plate  | -  | 02 sets                    |
| 05.   | Design & manufacturing Standard   |  |                            |
| Design and manufacturing in compliance with API-685 standard          |   |  |                            |
| 06.   | Terms and conditions - documentation required   |  |                            |
|   | . Certificate of Origin vii. Stardard QA certificate should be  |  | e provided                 |
| ii. Material test certificate   |   | & CCP Pump and motor data shi                            |                            |
| iii. Hydrostatic performance test certificate                         |   | viii. Instrumentation details                            |                            |
|   | NPSH Test & Pump Performance test certificates  | ix. Electrical test (type and routine p                  |                            |
| v. Pump characteristic curves vi. General arrangement drawings (GADs) |   | x. Dyramic balance test procedure and report             |                            |
| . General arrangement drawings (OADS)                                 |   | xi. Hydraulic performance test 3.1B to ISO 9906 class 2B | according                  |
| 07.   | Inspection  Certificate of inspection & performance testing noise level monitoring along-with inspection of QC documents as per above quoted standards by this party, Pre-s'tipment inspection at vendor's premises |  | tion of QCP<br>ds by third |

05 Years (included)