




شرکت پتروشیمی بوشهر Utility and Offsite واحد
فاز 2 منطقه ویژه اقتصادی انرژی پارس جنوبی عسلویه



GENERAL NOTES

- 1- Pump estimated shut-off pressure: 7.4 barg.
2- Maximum Design temperature is 85°C.



NOTES

- 1- In normal operation five pumps are in service. One pump is stand-by.
2- NPSHA is at pump suction nozzle centerline, 1250mm above ground level.
3- See "Utilities Specifications and Site Conditions" in the attachment
4- Maximum Chloride Concentration.
5- The electrical motor shall be equipped with 6 RTD's for winding and 2 RTD's for bearing.