ow	NER:		PROJECT:		CONTRACTOR:				
CONSULTANT:			Amu-Bukhara Irrigation System Rehabilitation Project Amu-Bukhara II Pump Station		tara engineering co. شرکت مهندسی تــــارا				
DOC	C. NO. :		DOC. TITLE: AMU BUKHARA PUMP STATION NO.2 MECHANICAL DATA SHEET		PAGE NO. : 1 0F 2				
1	PROCESS AND OPERATING CONDITIONS								
2	Liquid		Irrigation water	Capacity (Each pump)	7.5 m3/s				
3	Density	0.977 -0.981	Kg/dm ³	Max./ Min. Capacity (Each pump)	- m3/s				
4	PH value	6.5-8	- Static Head		m				
5	Viscosity	1.3	ср NPSH Available		10 m				
6	Solids content	100	ppm	NPSH Required	m				
7	Particle size	0.7	mm	NPSH 3 %	- m				
8	Vapour pressure	0.13-0.43	m	Differential Pressure	40 m				
9	Liquid Temperature (Min/Norm/Max)	5/20/30	°C	Pump Service	continuous -				
10	Indoor Temperature (Min/Max)	5 / 35	°C	Pump Operation	Parallel -				
11	Ambient Temperature(Min/Max)	-20 /35 (Outo	loor)	Location	Indoor -				
12	Elevation from Sea Level	600	m	Relative Humidity	10/85 %				
13	Ambient Conditions	Dusty							
14	TECHNICAL SPECIFICATION								
15	Pump Type	_	al - Split case- vertical volute or metal volute By Vendor)	Motor General Specification:					
16	Quantity		4+1	Motor Rated Power	By Vendor				
17	Manufacturer		By Vendor	Motor Type	Squirrel Cage Rotor				
18	Model		By Vendor	Motor Rated Voltage	6.6 KV				
19	Arrangement		Horizental	Frequency	50 HZ				
20	No. of Stages		By Vendor	Motor Speed	1485 rpm				
21	Impeller Type		By Vendor	<u>Bearing</u>	g General Specification:				
22	Impeller Diam. Min/Max		By Vendor	Bearing Type-axial	Pad				
23	Impeller Diam. Designed		By Vendor	Bearing Type-radial	Anti -Friction				
24	Shaft Diameter		By Vendor	Bearing Lubrication/Lub Type	Forced Lubricated				
25	Suction Size /standard		By Vendor						
26	Discharge Size /standard		By Vendor						
27	Pump Speed		By Vendor						
28	Required Power		By Vendor						
29	Direction of rotation		One Side						
30	Pump Moment Of Inercia		By Vendor						
-	Pump Weight with Base plate		By Vendor						
32				CCESSORIES					
33	Name Plate Including TAG		Required	Stator RTD	Required				
	Transport packing		Required	Base Plate	Required				

OWNER:		PROJECT:		CONTRACTOR:							
CONSULTANT:			Rehabili	Irrigation System tation Project a II Pump Station	tara engineering co. شرکت مهندسی تــــار ا						
DOC	2. NO. :		DOC. TITLE:	ON NO.2 MECHANICAL DATA SHEET	PAGE NO. :						
36	MATERIAL SPECIFICATION MATERIAL SPECIFICATION										
37	Casing	Cast I	ron - ASTM A216 WCB Impeller Wear ring		ASTM 420						
	Shaft	Stainless steel ASTM A276 Tp. 420		Bearing bracket	ASTM A216 WCB						
39	Impeller	ASTM A890 1B		Flanges	Cast Iron - ASTM A216 WCB						
40	Shaft sleeve		ASTM 420	Auxiliary piping	Carbon Steel						
41	Int-stage sleeve/bush		ASTM 420	Bolts and nuts		Carbon Steel					
42	Base plate		CS Welded								
43	Casing wear ring		ASTM 420								
44	PERFORMANCE DATA										
45	45 Pump+Motor overall Efficiency (In working poir 85.00% Minimum flow for continous operation -										
46	Pump Efficiency (Min/Max)		-	Minimum flow for starting		-					
47	Pump Absorbed Power		2297 kw	Maximum Head		By Vendor					
48	Drive Rated Power		2600 kw	ut-off Head		By Vendor					
49	49 CONSTRUCTION FEATURES										
50	Casing Design	Casing Design		Radial Bearing Type	Anti -Friction						
51	/olute Type		Vertical volute	Axial Bearing Type	By Vendor						
52	Suction Type		By Vendor	Coupling Type	<u>-</u>						
53	Casing Split		radial Split	Coupling Model	-						
54	Casing Support Type		-	Coupling Manufacturer	-						
55	Design Pressure		By Vendor	Coupling Guard	-						
56	Test Pressure		By Vendor	Shaft Dia. at Coupling End	-						
57	7 Shaft Sealing		Mechanical Seal	Thrust Balancing Method	Thrust Bearing						
58	8 Seal Manufacturer & Model		By Vendor	Wear ring Type	-						
59	TEST & CERTIFICATES										
60	Performance		Witness +Certificated	Material	UW +Certificated						
61	Vibration		Witness +Certificated	Hydrostatic	Witness +Certificated						
62	62 NPSH		Witness +Certificated	Bearing Temp. Rise	Witness +Certificated						
	Shop		UW +Certificated	Dimensional	UW +Certificated						
64	Note 1 :Performance Test according to ISO9906 Class 1B is done for one pump.										