

The Employer, WAPDA through Chief Engineer-II (Hydro) Planning, WAPDA, invites sealed Bids from eligible firms licensed by the Pakistan Engineering Council in the appropriate category for the works regarding providing & installation of following material for installation of 01-No. New Tubewell at WAPDA Colony, Bannu – Kurram Tangi Dam Project, Stage-1. The time to supply within 60-days.

Sr. No.	Description	Unit	Quantity
1	Providing & installation of M.S blind pipe 250 mm dia into tubewell bore with socket and solution complete (6 mm wall thickness).	Meter	80
2.	Providing and installation of M.S strainer 250 mm dia into tubewell bore with bail plug, socket and solution complete (6 mm wall thickness).	Meter	30
3	Providing & Placing of Centralizer	No.	18
4.	Providing/Filling Shrouding material (Graded Bajri) around strainer/blind pipe into bore hole.	Meter	110
5.	Provision of chemical for cleaning of tubewell	Job	Lump-sum
6.	Provision of Bentonite in bore hole during drilling for its stability.	Bags	110